

15-129-3006-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11/3/65

LEASE NAME INTERSTATE

WELL NUMBER 78

2690 Ft. from S Section Line

3090 Ft. from E Section Line

SEC. 32 TWP. 34S RGE. 43 ~~XX~~or(W)

COUNTY Morton

Date Well Completed 11/3/65

Plugging Commenced 6/15/89

Plugging Completed 6/20/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/15/89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4202 Bottom 4234 T.O. 4290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	4234	4290	7"	1229	0'
				3 1/2"	4288	2556'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Spotted 15 sxs cmt with 1 1/2" tbg on top of CIBP @ 4100'. TOH w/tbg. Shot off csg @ 2256'. Circulate hole w/9 ppg mud w/3 1/2" csg. All plugs spotted w/3 1/2" csg. Spot 25 sxs @ 2224-2100, spot 35 sxs @ 1260-1100, spot 25 sxs @ 500-400', and spot 15 sxs @ 65-3'. Common cmt used on all plugs. 7" csg 3' below surface and weld on steel cap. Restore location.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Morton, ss. AUG 15 1989

M. L Pease, Division Production Manager (Employee of Operator CONSERVATION DIVISION) or above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) M. L Pease

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 89

Cheryl Steers
Notary Public

My Commission Expires:

