

15-129-30065-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 10-12-65 Spud Date _____

LEASE NAME Interstate Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 77

2710 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 32 TWP. 34S RGE. 43 (E) or (W)

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 11-9-65

Character of Well OIL

Plugging Commenced 7-8-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-12-94

The plugging proposal was approved on 7-12-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Driller's

Is ACO-1 filed? Log Filed If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 4285

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				7"	1203	4'
				3 1/2"	4283	1235'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. MIRU csg pullers. TIH w/1 1/4" tbg to 4110'. RU pmp truck. Circ hole w/9 ppg mud. Pmp 10 sxs Class "H" cmt to spot plug on CIBP from 4110-3810'. TOH w/1 1/4" tbg. Pull free point and shot 3 1/2" csg @ 1235'. Circ hole w/9 ppg mud. Spot 45 sxs Class "H" cmt @ 1235-1035', 25 sxs Class "H" cmt @ 650-550', 10 sxs Class "H" cmt from 40-4'. Cut off and cap 7" csg 4' below gl. RDMO csg (If additional description is necessary, use BACK of this form.) pullers. (Over)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECORDED

KANSAS CORPORATION COMMISSION

(Signature) Leslie I. Barnes

Leslie I. Barnes, Sr. Tech. Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

AUG 08 1994

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 94

CONSERVATION DIVISION
WICHITA, KS

My Commission Expires: _____

Cheryl Steers
Notary Public

