

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 7/14/61

LEASE NAME Interstate

WELL NUMBER 71

4575 Ft. from S Section Line

4710 Ft. from E Section Line

SEC. 32 TWP. 34 SRGE. 43 ~~XX~~ or (W)

COUNTY Morton

Date Well Completed 7/14/61

Plugging Commenced 6/20/89

Plugging Completed 6/27/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/15/89 (date)

by Dan Goodran (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Sent with Plugging Application

Producing Formation Purdy Morrow Depth to Top 4200 Bottom 4226 T.D. 4310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf.	To Surf.	Size	Put in	Pulled out
Purdy Morrow	Oil	1242	4309	8 5/8	1242	None
				5 1/2	4309	2256

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/2" tbg. Spot 20 sxs common cmt on CIBP from 4100-3950. Shot off csg. @ 2256. Circ hole w/9 ppg dm. Spot 35 sxs cmt @ 2220-2100. Spot 40 sxs cmt @ 1300-1200 across csg shoe. Spot 35 sxs cmt @ 500-400. Spot 25 sxs cmt @ 80-3'. Cut off csg 3' below surface and welded on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Morton, ss.

M. L. Pease, Division Production Manager (Employee of Operator) of Interstate (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) M. L. Pease

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1989

(Cheryl Steers)  
Notary Public

My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1989  
10-12-89  
CONSERVATION DIVISION  
WICHITA, KANSAS