

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21,220-0000

LEASE NAME Linscott "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 9

1250 Ft. from S Section Line

2800 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 32 TWP. 34 SRGE. 43 (E) or (W)

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 2/28/94

Character of Well Gas

Plugging Commenced 12/13/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/15/94

The plugging proposal was approved on 12/15/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 3000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	679'	0'
				5 1/2"	2976'	1022'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TOH & ld rods, pmp & 2 3/8" tbg. Pmpd 4 sxs hulls & 25 sxs cmt plg from 2693-2500'. Shot 5 1/2" csg @ 1022'. Pmpd 35 sxs cmt plg from 1022-922'. Pull csg to 715' & circ hole w/mud. Spot 50 sxs cmt plg from 715-565'. Pull csg to 40' & spot 10 sxs cmt plg from 40-0'. Cut off 8 5/8" csg 3' below ground level and cap. Witnessed by KCC Rep - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731 (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

Leslie I. Barnes, Sr. Tech. Asst.
(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 95

(Cheryl Steers)
Notary Public

CONSERVATION DIVISION
W.D. Wit. A.R.S.
Commission Expires:

