

15-129-10439-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA
LEASE NAME INTERSTATE UNIT *

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 70
4620 Ft. from S Section Line
660 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 31 TWP. 34S RGE. 43 (E) or (W)

ADDRESS P. O. Box 351, Liberal, Kansas 67901

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 6/3/55

Character of Well TA'd Input

Plugging Commenced 9/17/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/21/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4203 Bottom 4220 T.O. 4591

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil, Water	4203	4220	8.625	1266	0
				5.5	4590	2015
Converted to Injection	12/65					
TA'd with CIBP	7/27/83					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH with 1-1/2" tubing. Spot 20 sxs cement on CIBP from 4100-3850'. TOH with tubing. Shot off casing at 2520'-no recovery. Shot off casing at 2015'. Spot 30 sxs cement from 2015-1865'. 40 sxs cement from 1300-1100'. 35 sxs cement from 650-480', and 10 sxs cement from 50-3'. Cap well. All cement plugs are 60/40 Poz with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.


M. L. Pease, Division Production Engineer (Employee of Operator) or ~~Representative~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

*Formerly Musgrove Petroleum Corporation -
BROWN No. 1

(Signature) M. L. Pease

(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 86



November 21, 1986

Notary Public

OCT 8 1986

Form CP-4
Revised 08-84