

15-129-10441-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT *

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 76

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 31 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 3/9/56

Plugging Commenced 9/21/86

Plugging Completed 9/22/86

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well TA'd Oil Producer

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4202 Bottom 4211 T.O. 4283

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil, Water	4202	4211	8.625	1218	0
				5.5	4282	2228
TA'd 8/1/83 with	CIBP because of	high WOR				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spot 20 sxs cement on CIBP from 4100' to 3850'. TOH with tubing. Shot off casing at 2228'.
Spot 30 sxs cement from 2228-2077', 40 sxs cement from 1400-1100', 35 sxs cement from 650-480', and 10 sxs cement from 60-0'. Cap well. All cement plugs are 60/40 Poz with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Engineer (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, Kansas 67901

*Formerly Musgrove Petroleum Corporation -
BROWN No. 3

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 86
BEVERLY J. WILLIAMS
Seward County, Kansas
My Appt. Exp. _____

Beverly J. Williams
Notary Public

My Commission Expires: November 21, 1986

OCT 8 1986