

15-129-10440-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA  
LEASE NAME INTERSTATE UNIT \*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 73  
3960 Ft. from S Section Line  
1320 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation  
ADDRESS P. O. Box 351, Liberal, Kansas 67901  
PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

SEC. 31 TWP. 34S RGE. 43 (E) or (W)  
COUNTY Morton

Character of Well TA'd Oil Producer  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 3/9/56  
Plugging Commenced 9/19/86  
Plugging Completed 9/23/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes  
Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4228 Bottom 4237 T.D. 4551

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation         | Content         | From     | To   | Size  | Put In | Pulled out |
|-------------------|-----------------|----------|------|-------|--------|------------|
| Morrow            | Oil, water      | 4228     | 4237 | 8.625 | 1240   | 0          |
|                   |                 |          |      | 5.5   | 4527   | 2025       |
| TA'd 7/29/83 with | CIBP because of | high WCR |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
TIH with 1-1/2" tubing. Spot 20 sxs cement on CIBP at 4100-3850'. TOH with tubing. Shot off casing at 2025'. Spot 30 sxs cement from 2025-1875', 40 sxs cement from 1300-1100', 35 sxs cement from 640-480', and 10 sxs cement from 50-3'. Cap well. All cement plugs are 60/40 Poz with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L Pease, Division Production Engineer (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) M. L Pease

(Address) Box 351, Liberal, Kansas 67901

\*Formerly Musgrove Petroleum Corporation - BROWN No.2.



SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 86  
Beverly J. Williams  
Notary Public

My Commission Expires: November 21, 1986