

15-025-20211-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Clark County, Sec. 16 Twp. 35S Rge. 25 (W)

Location as "NE/CNWSW" or footage from lines 1820' FEL, 710' FSL
Lease Owner: AMERICAN PETROFINA COMPANY OF TEXAS

Lease Name: Theis Well No. 1-16
Office Address: 4613 Jacksboro Hwy., Wichita Falls, Tx. 76302

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 6-24 19 77

Application for plugging filed 4-12 19 78

Application for plugging approved 4-17 19 78

Plugging commenced 4-21 19 78

Plugging completed 4-21 19 78

Reason for abandonment of well or producing formation Loss of casing string.

If a producing well is abandoned, date of last production January 19 78

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Beakey notified.

Producing formation Chester Depth to top 5850 Bottom 5921 Total Depth of Well 6102 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	121	-
				8 5/8"	626	-
				5 1/2"	6077	410

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran tubing to 5650' pump 25 sxs. Regular 6% gel, 3% Ca Cl cement plug from 5721 to 5650'. Ran 2-3/8" tubing to 395' pump 10 sxs. Reg. cement plug from 395' to 365'. Pump 180 sxs. cement plug down 8 5/8" casing displaced to 170'. Ran tubing to 170' pump 50 sxs. Reg. cement plug from 170' to surface. Cement circulated.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor None used

Address

STATE OF Texas, COUNTY OF Wichita, ss.

W. B. Watson (employee of ~~owner~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. B. Watson*

4613 Jacksboro Highway, Wichita Falls, Tx. 76302
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 78

Apple Buntyn
Notary Public.

My commission expires 6-30-78