


15-025-20017-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

CLARK County, Sec. 4 Twp. 35S Rge. (E) 25 (W)
Location as "NE/CNW/SW" or footage from lines C W 2
Lease Owner Doric Corporation
Lease Name Theis Well No. 1
Office Address 1170 First Nat'l. Bank Bldg., Okla. City, Ok.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 17, 19 70
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 17, 19 70
Plugging completed January 17, 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves of Sublette
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5990 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	640'	8-5/8"	640'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 600 Feet;
A Plug and 35 sax Cement to 500 Feet;
Heavy Mud from 500 Feet to 45 Feet, Plug
and 15 sax Cement to Base of Cellar; 2
sax Cement in Rat Hole. Job Completed
@ 5:00 A.M. on 1/17/70.

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 19th day of January, 19 70
Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

THEIS NO. 1

CASING RECORD:	OPERATOR:	Doric Corporation	DESCRIPTION:
8-5/8" @ 640' w/400 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	C W $\frac{1}{2}$ Sec. 4-35S-25W Clark Co., Kansas
TOTAL DEPTH:	COMMENCED:	January 4, 1970	ELEVATION: 2033 KB
5990'	COMPLETED:	January 17, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	650	
Cement & Red Bed	650	875	
Red Bed & Sand	875	1300	
Lime & Shale	1300	1594	
Shale	1594	2014	
Lime & Shale	2014	2275	
Shale & Lime	2275	2408	
Lime & Shale	2408	3705	
Shale & Lime	3705	3780	
Lime & Shale	3780	4933	
Shale & Lime	4933	5057	
Lime & Shale	5057	5432	
Shale & Lime	5432	5512	
Lime & Shale	5512	5990	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 19th day of January, 1970.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.