

RECEIVED

FEB 24 2003

KCC WICHITA

2-24-03

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20240-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

2/03

WELL OPERATOR EXCO Resources, Inc. KCC LICENSE # 32581
(owner/company name) (operator's)

ADDRESS 6500 Greenville Ave., Suite 600, CITY Dallas
LB17

STATE TX ZIP CODE 75206 CONTACT PHONE # (808) 254-4825

LEASE Adams Ranch WELL# 5-11 SEC. 11 T. 35S R. 29 (East/~~West~~)

- NW - NW - NW SPOT LOCATION/OOOO COUNTY Meade

330 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1480' CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6054' CEMENTED WITH 325 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: See data sheet

ELEVATION 2328' KB T.D. 6054' PBD 5150' ANHYDRITE DEPTH Unknown
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set bottom plug with 25 sks. Put 50 sk. plug from 1510' to 1310'. Put 40 sk. plug from 500' to 340'. Place 10 sk. plug from 40' to 0'. Mud spacing with each plug.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Lemieux PHONE# (620) 391-2195 ^{cell}

ADDRESS General Delivery City/State Forgan, OK 73938

PLUGGING CONTRACTOR Sargent & Lillard Casing Puller KCC LICENSE # 32833

ADDRESS P O Box 1450, Woodward, OK 73802 PHONE # () (580) 254-1881
(company name) (contractor's)

4/03

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 2nd or 3rd Quarter of 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-19-03 AUTHORIZED OPERATOR/AGENT: Paul D. Roberts
(signature)

Paul D. Roberts
District Manager

RECEIVED
FEB 24 2003
KCC WICHITA

Adams Ranch 5-11
NW NW NW of Section 11-35S-R29W
Meade County, Kansas

Data Sheet for Perforations and Bridge Plug Sets

Formation

Chester
Morrow

Perforations

5894' to 98' and 5978' to 88'
5836' to 41' and 5845' to 49'

1. Note: Model D packer in wellbore at 5822'.
Has tubing fish stuck in packer. Top of fish at 5676'.
2. Note: Cast iron bridge plug set at 5150' KB in April 1991.

Kansas City	5001' to 08', 5012' to 20' and 5029' to 31'
Lansing	4436' to 46'
3. Note: Casing leak found between 3275' and 3309'. Cement squeezed the leak in April, 1991.



Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

EXCO Resources, Inc.
6500 Greenville Ave.-Su 600, LB 17
Dallas, TX 75206

February 26, 2003

Re: ADAMS JESSIE S #5-11
API 15-119-20240-00-00
CNWNWNW 11-35S-29W, 330 FNL 330 FWL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888