

RECEIVED

FEB 24 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20157-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR EXCO Resources, Inc. KCC LICENSE # 32581

ADDRESS 6500 Greenville Ave, Suite 600, CITY Dallas
(owner/company name) (operator's)

STATE Texas ZIP CODE 75206 CONTACT PHONE # 308 254-4825

LEASE Adams Ranch WELL# F-1 SEC. 10 T. 35S R. 29 (East/West)

NE - NW SPOT LOCATION/Q000 COUNTY Meade

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1540' CEMENTED WITH 675 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 6530' CEMENTED WITH 400 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: See data sheet

ELEVATION 2325 KB T.D. 6754' PBDT 6060' ANHYDRITE DEPTH Unknown
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set bottom plug with 25 sacks. Put 50 sk. plug from 1570' to 1370'. Set 40 sk. plug from 500' to 340'.

Place 10 sk. plug from 40' to 0'. Mud Spacing with each plug.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED?

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Lemieux Cell PHONE# () (620) 391-2195

ADDRESS General Delivery City/State Forgan, OK

PLUGGING CONTRACTOR Sargent & Lillard Casing Pullers KCC LICENSE # 32833

ADDRESS P O Box 1450, Woodward, OK 73803 PHONE # () (580) 254-1881
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 2nd or 3rd quarter of 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-19-03 AUTHORIZED OPERATOR/AGENT: Paul D. Roberts

(Signature)
Paul D. Roberts
District Manager

2/10/03

4/03

RECEIVED
 FEB 24 2003
 KCC WICHITA

Adams Ranch F1
 NE NW of Section 10-35S-R29W
 Meade County, Kansas

Data Sheet for Perforations and Bridge Plug Sets

<u>Formation</u>	<u>Perforations</u>
St. Genevieve	6321' to 28' and 6335' to 40'
1. Note:	After testing above perms, set CIBP at 6316'.
St. Genevieve	6290' to 6304'
2. Note:	After testing above perms, set CIBP at 6250'.
Chester	6192' to 98' and 6203' to 09'
3. Note:	After testing above perms, set CIBP at 6060'.
Chester	5891' to 97', 5916' to 23', 5927' to 33' 5974' to 80' and 6014' to 20'
Marmaton	5184' to 91', 5204' to 09', and 5230' to 38'
Kansas City	5018' to 23'
4. Note:	Cement squeezed Kansas City perms above after two months pump testing. Squeeze done January 1987.
5. Note:	Perfs now open to wellbore are Marmaton and upper Chester.



Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

EXCO Resources, Inc.
6500 Greenville Ave.-Su 600, LB 17
Dallas, TX 75206

February 26, 2003

Re: ADAMS RANCH #F-1
API 15-119-20157-00-00
CNENW 10-35S-29W, 660 FNL 1980 FWL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888