

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20488-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR EXCO Resources, Inc. KCC LICENSE # 32581
(owner/company name) (operator's)

ADDRESS 6500 Greenville Ave. Suite 600 LB 17 CITY Dallas

STATE Texas ZIP CODE 75206 CONTACT PHONE # (308) 254-4825

LEASE Adams WELL# 1-8 SEC. 8 T. 355 R. 29 (East/West)

SW - SE SPOT LOCATION/0000 COUNTY Meade

860 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1967 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1502 CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6343 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: See Data Sheet

ELEVATION 2345' KB T.D. 6382' PBDT 6307' ANHYDRITE DEPTH Unknown
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP at 5784' & dump bail one sk. cmt. on top. Stretch csq. & shot off as close to 4220' as possible. Spot 50 sk. stub plug @ shot point. Pull 5 1/2" csq. to base of surface csq. @ 1502'. Pump 50 sk. plug from 1502' up to 1352'.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Lemieux PHONE# (580) 487-3562(home) (316)621-2975 cel

ADDRESS PO Box 2 City/State Forgan, OK

PLUGGING CONTRACTOR Sargent & Lillard Casing Pullers KCC LICENSE # 32833
(company name) (contractor's)

ADDRESS PO Box 1450, Woodward OK 73802 PHONE # (580) 254-1881

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 3rd or 4th quarter, 2001 / 12-27-01 plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/8/01 AUTHORIZED OPERATOR/AGENT: Paul O. Palta
(signature)

RECEIVED

AUG 14 2001

KCC WICHITA

Form CP-1 (cont.)

Pull csg. to 500' and pump 30 sk. plug from 500' up to 405'. Spot 10
sk. plug from 40' to plow depth.

RECEIVED

AUG 14 2001

KCC WICHITA

Exco Resources, Inc.

**Adams # 1-8
SW SE Sec. 8-T35S-R29W
Meade County, Kansas**

Data Sheet for Perforations

<u>Formation</u>	<u>Perf Depths</u>	<u>Remarks</u>
Chester	6124' – 6129'	Now Open
Chester	6136' – 6141'	Now Open
Chester	5863' – 5876'	Now Open
Chester	5885' – 5898'	Now Open
Chester	5908' – 5914'	Now Open
Morrow	5818' – 5830'	Now Open
Marmaton	5166' – 5174'	Squeezed w/75 sks.
Kansas City	4948' – 4955'	Squeeze w/100 sks. Pressure tested both Squeezes to 1000 Psig. Held good.

RECEIVED

AUG 14 2001

KCC WICHITA