

15-119-00011-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
Wichita, Kansas 67217

Rev. 3-15-72  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1977  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Exxon Corporation  
Address Box 1600 Midland, Tx. 79702  
Lease (Farm Name) Adams Ranch Well No. 1  
Well Location C-SW-NE Sec. 1 Twp. 35S Rge. 29 (E)      (W)   
County Meade Total Depth 6175 Field Name Adams Ranch  
Oil Well  Gas Well  Input Well  SWD Well  Rotary D & A   
Well Log filed with application as required Yes  
Date and hour plugging is desired to begin When permission granted.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:  
Toyle Fleming Address Box 519 Perryton, Tx. 79070  
Plugging Contractor Sargent Casing Pullers License No. - 511  
Address P.O. Box 506 Liberal, Ks. 67901

Invoice covering assessment for plugging this well should be sent to:  
Name Exxon Corp.  
Address Box 1600 Midland, Tx. 79702

and payment will be guaranteed by applicant or acting agent.

Signed: [Signature]  
Applicant or Acting Agent  
Date: 8-19-77



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

August 23, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Adams Ranch
Description	C SW NE Sec. 1-35-29W
County	Meade
Total Depth	6175
Plugging Contractor	Sargent's Casing Pulling Service


Exxon Corporation  
Box 1600  
Midland, Texas 79702

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Clarence Thomas, 403 Davis, Garden City, Kansas 67846  
is hereby assigned to supervise the plugging of the above  
named well.

CONSERVATION DIVISION  
Wichita, Kansas

AUG 23 1977

RECEIVED  
STATE CORPORATION COMMISSION

Perms 6026-6106

P87D 61301  
S.E. 1/4 T12N R17E  
CMT. 10/200 by Permis

Est. log of CMT. R17E

8 3/8" @ 2452'  
CMT. by 200 = 15'

Estimated Top of CMT. 18.13

13' @ 546'  
CMT. w/ 610 sh. - Estimated

15-119-00011-0000

ADAMS RANCH NO. 1PLUG AND ABANDONMENT PROCEDURE

1. MIRU casing pullers. Lower the 1-1/4" tubing to 6106'. Circulate the hole with 9.5# drilling mud (36 viscosity). Spot a 10 sk 15.4/gal slurry Class "H" cement plug from 6106' to 6018'. Displace with 9.5# drilling mud. Pull the tubing up the hole enough to clear cement. W.O.C. Tag plug #1. If plug #1 is in place, pull the tubing and lay down in singles. Keep the hole full of 9.5# drilling mud.
2. Work and stretch the 5-1/2" casing. Shoot off at free point. Pull the 5-1/2" casing up the hole to 2477'. Keep the hole full of 9.5# drilling mud. Spot a 20 sk 15.4/gal slurry Class "H" cement plug from 2477' to 2427'. Displace with 9.5# drilling mud. Pull the 5-1/2" casing up the hole enough to clear cement. W.O.C. Check plug #2 with wire line. If plug #2 is in place, pull the 5-1/2" casing and lay down in singles. Keep the hole full of 9.5# drilling mud.
3. Work and stretch the 8-5/8" casing. Shoot off at free point. Pull the 8-5/8" casing up the hole to 571'. Keep the hole full of 9.5# drilling mud. Pump a 60 sk 15.4/gal slurry Class "H" cement plug from 571' to 521'. Displace with 9.5# drilling mud. Pull the 8-5/8" casing up the hole enough to clear cement. W.O.C. Check plug #3 with wire line. If plug #3 is in place, pull and lay down the 8-5/8" casing. Fill the 13" with 9.5# drilling mud to within 50' of surface. Fill the 13" from 50' to 3' with 35 sacks. Cut surface casing off and mark date and well number in cement cap.

ESTIMATED COST

Casing Pullers	\$2,800
Cement Services	1,000
Cement	600
Drilling Mud	350
Trucking	300
Miscellaneous	500

TOTAL	\$5,550
-------	---------

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1977

CONSERVATION DIVISION  
Wichita, Kansas