

API NUMBER 119-20146-0000

LEASE NAME Mohler

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

2306 Ft. from E Section Line

SEC. 28 TWP. 34S RGE. 29W (E) or (W)

COUNTY Meade

Date Well Completed 12/01/73

Plugging Commenced 02/03/94

Plugging Completed 02/15/94

LEASE OPERATOR Elder & Vaughn

ADDRESS P. O. Box 18938

PHONE# (405) 842-8877 OPERATORS LICENSE NO. 06160

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 3, 1994 (date)

by District I (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Chester Depth to Top 5963' Bottom 5988' T.D. 6050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in'	Pulled out
Chester	Oil	5960	5988'	8 5/8"	711'	-0-
				5 1/2"	6054'	1317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set 5 1/2" CIBP at 5895' with 15' cement on top of CIBP, load hole with mud, shot casing at 1317', pull 33 jts casing, put 3 sacks cottonseed hulls and 3 sacks gel in hole, surface started circulating, RIH with 25 jts 2 3/8" tubing, pump 100 sacks from 700' to 300', pull 22 jts 2 3/8" tubing, pump 22 sack plug from 60' to 4', check plug, plug ok, cut off casing and weld ID plate.

Name of Plugging Contractor Petrofield Services Corporation License No. 31330

Address 110 South Hartford, Suite 300 Tulsa, Oklahoma 74120

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petrofield Services Corporation

STATE OF Oklahoma COUNTY OF Tulsa, ss.

MAR 17 1994

(Employee of Operator) CONSERVATION DIVISION of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Lisa A. Petryman

(Address) 110 South Hartford #300 Tulsa, Okla 74120

SUBSCRIBED AND SWORN TO before me this 15TH day of MARCH, 19 94

D. L. Thomas
Notary Public

My Commission Expires: July 19, 1994
USE ONLY ONE SIDE OF EACH FORM