

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,277-0000

LEASE NAME ADAMS

WELL NUMBER # 1-27

1250' Ft. from S Section Line

1250' Ft. from ^W~~S~~ Section Line

SEC. 27 TWP. 34S RGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed 10/10/77

Plugging Commenced 3/14/90

Plugging Completed 3/27/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MESA OPERATING LTD PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 04824

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Verbal on 3/9/90 to _____ (date)

by Steve Durrant w/KCC (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Morrow/Chester Depth to Top 5872' Bottom 6248' T.D. 6350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	gas	5872'	5910'	8 5/8"	1530'	None
Chester	gas	5972'	6248'	5 1/2"	6348'	3218'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set 5 1/2" GIBP @ 5850' dumped 2 sx cement on top. POH w/5 1/2" casing; spotted 50 sx cement plug from 1580'-1430'; mix and spot 50 sx cement plug from 650'-550'; set 10 sx from 30' to surface. Welded on plate - well P&A 3/27/90; Glen Barlow w/KCC on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pullers License No. 6547

Address P.O. Box 506 Liberal Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mesa Operating Ltd Partnership

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. McKee (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn L. McKee

(Address) P.O. Box 2009, Amarillo, Texas 79189

SUBSCRIBED AND SWORN TO before me this 30th day of March, 19 90

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:



DWAINA PITTS
Notary Public, State of Texas
My Commission Expires 8-6-93