

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 27 Twp. 34S Rge. 29 (W)

Location as "NE/CNW/SW" or footage from lines. Ctr NE/4

Lease Owner Texaco Inc.

Lease Name H. G. Adams "E" O/A Well No. 1

Office Address 614 Bitting Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) SI Gas

Date well completed 6-20-1960

Application for plugging filed 2-16-1967

Application for plugging approved 2-17-1967


Plugging commenced 3-4-1967

Plugging completed 3-4-1967

Reason for abandonment of well or producing formation Uneconomical to produce.

If a producing well is abandoned, date of last production None - SI 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well E. Eves

Producing formation Council Grove Depth to top 2995 Bottom 3265 Total Depth of Well 3345 Feet

Show depth and thickness of all water, oil and gas formations. PBTB 3275

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Gas	2995	3265	13-3/8	40	None
				8-5/8	448	None
				2-7/8	3363	2611'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: 3275-3100 w/5 sxs cmt,
3100-450 w/hvy mud,
450-350 w/40 sxs cmt,
350-45 w/hvy mud,
45-0 w/15 sxs cmt.

Comp 3 PM 3-4-67

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1967
4-7-67
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Service

Address Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. F. E. Anderson (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. Anderson

614 Bitting Bldg., Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April 1967

Peggy Sue Jones

Notary Public.

My commission expires 10-13-69

Texaco, Inc.
Tulsa, Oklahoma

Tulsa, Oklahoma
June 15, 1960

Contractor: Stickle Drilling Co.
Date Commenced: June 3, 1960
Date Completed: June 12, 1960

H. G. Adams "E" No. 1
Ctr. NE Sec. 27-36S-29W
Meado County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Shale and sand	400
Shale and shells	430
Shale	445
Red bed and shale	895
Red Bed	1380
Anhydrite	1630
Shale and shells	2160
Shale and Lime	2625
Lime and Shale	2705
Shale and Shells	2850
Lime and shale	2910
Shale and Lime	3005
Lime and shale	3160
Lime	3345 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Texaco, Inc. H. G. Adams "E" No. 1 Well, Center of NE/4 of Section 27-36S-29W, Meado County, Kansas.

Fred E. Stickle
Fred E. Stickle

Edith A. Lawrence
Notary Public

My Commission expires March 24, 1964

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1967
CONSERVATION DIVISION
Wichita, Kansas