

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20044-00-00

LEASE NAME ADAMS

WELL NUMBER D-1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 31 TWP. 34 RGE. 30 ( E ) or ( U )

COUNTY MEADE

Date Well Completed 11-17-70

Plugging Commenced 8-22-01

Plugging Completed 8-24-01 (date)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S. TAYLOR, STE. 400 AMARILLO, TX 79101

PHONE # ( 806 ) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-15-01

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation LANSING Depth to Top 4346 Bottom 4348 T.D. 4403

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
LANSING	GAS	4346	4348	8 5/8	1280	0
				4 1/2	4399	2010

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. SET CIBP @ 4300. PULL FREE POINT AND SHOT OFF 4 1/2 CSG @ 2010. CIRC MUD. PMP 50 SXS CMT PLUG @ 1300 TO 1150. PMP 25 SXS CMT PLUG @ 660 TO 580. PMP 10 SXS CMT PLUG @ 40 TO SURFACE. CUT OFF AND CAP 8 5/8 CSG 3' BELOW GL AND CAP. RDMQ. RESTORE LOCATION. KCC REP. JIM HOLLAND.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENTS & HORTON PLUGGING INC. License No. 31151

Address RT 1 BOX 49 BA, TYRONE, OK 73951 PHONE: 580-854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters  
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, SUITE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 8 day of October, 2001

Lori Pearson  
Notary Public

My Commission Expires: 2/26/05

OK