

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20046-0000

LEASE NAME ADAMS

WELL NUMBER #3

SPOT LOCATION SW NW

SEC. 31 TWP 34S RGE 30W (E or W)

COUNTY Meade

Date Well Completed 7-23-70

Plugging Commenced 6-12-84

Plugging Completed 6-14-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Blaik Oil Company

ADDRESS 5825 N. Grand Blvd., Okla. City, Okla. 73118

PHONE # (405) 843-6624 OPERATORS LICENSE NO. 5361

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing Depth to top 4300' bottom 4322' T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing</u>	<u>Oil</u>	<u>4300</u>	<u>22</u>	<u>8-5/8"</u>	<u>1259'</u>	<u>-0-</u>
				<u>4 1/2"</u>	<u>4387'</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 35 sx @ 4000' Well had excessive pressure on surface pipe, plugging attempt temporarily abandoned 7-27-74.

6-12-84 Perf 4 holes @ 1300' in 4 1/2" csg. - Pump 385 sx Class H (16.5#).

6-14-84 Pump 300 sx Class H down Surface pipe -

6-15-84 KCC representative checked job -OK- Requested delay in capping.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A
Address Liberal, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Robert E. Blaik (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert E. Blaik

(Address) 5825 N. Grand Blvd., OKC, OK 73118

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1984

Carolyn B. Chamberlain
Notary Public

My Commission expires: 2-17-86

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1984
CONSERVATION DIVISION
Wichita, Kansas

LEASE: ADAMS #3
OWNER: BLAIE OIL COMPANY
CONT: EARL F. WAKEFIELD
COM: 1-21-70
COMP: 1-29-70

LOCATION: C SW NW
SECTION 31-34S-30W
MEADE COUNTY, KANSAS
CASING: 8 5/8" SET @ 1259'
4 1/2" SET @ 4389'

Sand & Clay	335
Red Bed	565
Red Bed, Shale & Sand	1080
Red Bed & Sand	1260
Anhydrite	1267
Anhydrite & Red Bed	1655
Shale & Lime	2120
Lime	3574
Lime & Shale	4245
Lime	4400
R.T.D.	4400


RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1974
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

I, Gordon L. Koelling, do hereby certify that this is a true and correct log on the Adams #3, located C SW NW of Section 31-34S-30W, Meade County, Kansas, as shown by the daily drilling reports.

EARL F. WAKEFIELD

BY: *Gordon L. Koelling*
Gordon L. Koelling



Subscribed and sworn to before me this 6th Day of February, 1970.

My Commission Expires:
October 22, 1972

Carol Jean Noel
Carol Jean Noel
Notary Public