

15-119-20050-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 4-20-70

LEASE NAME Adams "E"

WELL NUMBER 1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 31 TWP. 34S RGE. 30 REX or (W)

COUNTY Meade

Date Well Completed 4-29-70

Plugging Commenced 7-15-91

Plugging Completed 7-17-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 12, 1991 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lansing Depth to Top 4372 Bottom 4374 T.O. 4443

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1304	0
				4 1/2	4442	2628

JUL 25 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Pmpd 1 sx hulls & 10 sxs cmt @ 4374-4274'. Displaced w/9 ppg mud to surface. Shot csg off @ 3025' (stuck). Shot csg off @ 2628' (free). TOH w/csg to 1375'. Spot 50 sxs cmt @ 1375-1225. TOH w/csg to 550', spot 35 sxs cmt @ 550-450'. TOH w/csg. Spot 10 sxs cmt @ 40-3'. Cut 8 5/8" csg off @ 3' & cap well. KCC Representative - Richard Lacy. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address P.O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

Beverly J. Williams - Engineering Technician
(Address) P.O. Box 351, Liberal, Kansas 67905-0351

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1991

CHERYL STEERS
Notary Public - State of Kansas
My Appt. Expires 6-1-93

Cheryl Steers
Notary Public

My Commission Expires: _____

DRILLER'S LOG

WELL NAME Adams "E" No. 1 COMPANY OPERATING Anadarko Production Company
 ADDRESS OF COMPANY Box 351, Liberal, Kansas 67901

WELL LOCATION C $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
3300 Ft. North of South Line,
3261 Ft. East of West Line, Sec. 31, Twp. 34S, Rge. 30W, Meade County, Kansas

DRILLING STARTED 4-10, 19 70, DRILLING COMPLETED 4-20, 19 70
 WELL COMPLETED 4-29, 19 70, WELL CONNECTED _____, 19 _____

ELEVATION 2509.4' Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Lansing	4372	4374	8	Acidized W/200	15% NE

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1304'	730	None
4 1/2"	4442'	135	None
2 3/8"	4374'	SN @ 4358'	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Red bed	0	330	Lime	4247	4443
Shale	330	640	Total Depth	4443	
Anhydrite & Shale	640	965			
Shale	965	1251			
Lime	1251	1305			
Shale	1305	1855			
Shale & Shells	1855	2190			
Lime	2190	2464			
Lime & Shale	2464	2690			
Lime	2690	3606			
Lime & Shale	3606	3750			
Shale	3750	4001			
Lime & Shale	4001	4247			

RESULTS OF INITIAL PRODUCTION TEST: Swabbed & flowed 101 BO in 9 hours.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 18 1991

CONSERVATION DIVISION
 Wichita, Kansas