

15-119-10276-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Meade County, Sec. 12 Twp. 34 Rge. 30 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C SE NE

Lease Owner Panhandle Eastern Pipe Line Co.

Lease Name Hull Well No. #1-12

Office Address PO Box 979 - Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 21, 1952

Application for plugging filed July 20, 1952

Application for plugging approved July 20, 1952

Plugging commenced July 21, 1952

Plugging completed August 23, 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe

Producing formation None Depth to top Bottom Total Depth of Well 6220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Marmaton	Dry			13 5/8	617'	None
Morrow	"			9 5/8	2977'	1,095'
Mississippi	"					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

	From	To
Rotary Mud	6220	6016
Cement Plug	6016	5884
Rotary Mud	5884	5400
Cement Plug	5400	5333
Rotary Mud	5333	2948
Cement Plug	2948	2936
Rotary Mud	2936	600
Cement Plug	600	575
Rotary Mud	575	23
Cement Plug	15	8

The 13 3/8" OD surface casing is cut off 8 feet below the ground level and the cellar is filled with dirt.

The cement plugs were placed in this hole through drill pipe by Halliburton Oil Well Cementing Company. The 9 5/8" OD Casing was pulled by the Daco Well Servicing Company of Borger, Texas

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Co.

Address Duncan, Oklahoma

8 27 52 AUG 27 1952

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.

L. W. Phillips (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

307 N. Kansas Ave., Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 1952

MY COMMISSION EXPIRES APRIL 16, 1956

My commission expires

23-8390-s 6-51-20M

Notary Public.

PLUGGING  
FILE SEC 12 T 34 R 303  
BOOK PAGE 447 LINE

PANHANDLE EASTERN PIPE LINE COMPANY

Well Name: Hall #1-12 Company: Panhandle Eastern Pipe Line Company

Location: Center of SE/4 of the NE/4 Section 12-34-30  
Maede County, Kansas Contractor: Moran Bros., Inc.  
Wichita Falls, Texas

Original Open Flow: Dry Hole Elevation: 2645.0'  
Original Rock Pressure: Drilling Commenced: May 23, 1952  
Open flow after acid: Drilling Completed: July 20, 1952  
Rock pressure after acid:  
Source: Drillers Report Well Completed: Dry Hole

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Surface Sands, Clay & Gravel	0	630
Red Bed	630	668

6471  
Set 632' 13 3/8" OD H-40, Black casing, T&C, 8 Rd Thrd, with 550 sacks of 2% Howco Gel Cement. (48#)

Red Bed & Anhydrite	668	1225
Shale & Anhydrite	1225	2605
Lime	2605	2650
Lime & Anhydrite	2650	2685
Shale & Anhydrite	2685	2705
Shale & Lime	2705	2738
Shale & Anhydrite	2738	2749
Lime	2749	2987

Set 2966' 9 5/8" OD J-55, Smls Black casing, 8 rd Thrd, with 600 sacks of 2% Howco Gel Cement. (36#)

Shale & Lime	2987	3044
Lime	3044	3054
Cherty Lime & Shale	3054	3112
Lime	3112	3188
Lime & Shale	3188	3230
Lime	3230	3378
Shale & Lime	3378	3650
Lime	3650	3678
Lime & Shale	3678	3861
Shale	3861	4064
Shale & Lime streaks	4064	4080
Shale & Lime	4080	4140
Shale	4140	4281
Shale & Lime	4281	4319
Shale	4319	4372
Shale & Lime	4372	4533
Lime	4533	4619
Shale & Lime	4619	4680
Shaly Lime	4680	4715
Shale & Lime	4715	4742
Lime	4742	4842
Lime & Shale	4842	4874
Lime	4874	5365
Cored Shale & Lime	5345	5405
Lime	5405	5562
Lime & Shale streaks	5562	5585
Lime & Shale	5585	5815
Lime	5815	5820
Cored Lime & Shale	5820	5884
Cored Shale & Sand	5884	5917
Shale & Sand streaks	5917	5941
Lime & Shale	5941	6052
Lime	6052	6104
Lime & Shale	6104	6220

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 27 1952

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**

FILE SEC 12-34-30 R 306

BOOK PAGE 40 LINE 15