


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

MEADE County. Sec. 9 Twp. 34S Rge. 30 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1250' FS&WL
Lease Owner ANADARKO PRODUCTION COMPANY - Gulf Energy
Lease Name FOX "D" Well No. 1
Office Address P. O. BOX 351, LIBERAL, KANSAS 67901
Character of Well (Completed as Oil, Gas or Dry Hole)
Depleted Gas Zone (Fox "D" #1 was comp. as gas well)



Locate well correctly on above
Section Plot

Date Well completed 5/2 1974
Application for plugging filed 5/23 1977
Application for plugging approved 5/25 1977
Plugging commenced 7/21 1977
Plugging completed 7/21 1977
Reason for abandonment of well or producing formation
Depletion of gas zone
If a producing well is abandoned, date of last production
November 1976

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well 6600'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1570'	
				4-1/2"	5970'	2705'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

4-1/2 5970', 8-5/8 csg 1570', perf 5845-49'. P&A, spotted 20 sxs cmt to 5700', cut csg
2705', spotted 50 sxs cmt 1500', spotted 15 sxs cmt 40'. Comp 7/20/77.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1977

(If additional description is necessary, use CONSERVATION DIVISION
Name of Plugging Contractor Sargent's Casing Pulling
Wichita, Kansas sheet)

STATE OF KANSAS COUNTY OF SEWARD, ss.
D. S. Tipton (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says, That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

LEONA FERNE CORNELSEN
STATE NOTARY PUBLIC
Seward County, Kansas
My Appointment Expires
June 23, 1980

(Signature)

D. S. Tipton, Division Production Engineer
P. O. Box 351, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1977

Leona Ferne Cornelsen
Notary Public.

My commission expires June 23, 1980

15-119-20016-0000

DRILLER'S LOG

WELL NAME: Box "D" No. 1 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
 WELL LOCATION: $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$,
1250 ft. North of South line,
1250 ft. East of West line: Sec. 9, Twp. 34S, Rge. 30W, Meade County, Kansas
 DRILLING STARTED 1/11, 19 68; DRILLING COMPLETED 1/28, 19 68
 WELL COMPLETED 2/9, 19 68; WELL CONNECTED _____, 19 _____
 ELEVATION: 2700.7 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
U. Morrow	3045	49	15	500	10% MC

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 25 1977

CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-3/8	1510'	775	None
4-1/2	2970'	150	None
2-3/8	3045'		None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface clay & shales	0	1571			
shales	1571	2467			
lime & shales	2467	2975			
lime	2975	3300			
lime & shales	3300	4716			
lime	4716	5737			
lime & shales	5737	6024			
lime	6024	6490			
Total Depth	6490				

RESULTS of INITIAL PRODUCTION TEST: 2/9/68 4 Point Check Test WNACT 26,000 MCTD