

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Meade County. Sec. 6 Twp. 34S Rge. 30 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Panhandle Development Co., Inc.  
Lease Name Gage Well No. 1  
Office Address 19 E. Eleventh, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.  
Date well completed July 9, 19 60  
Application for plugging filed July 9, 19 60  
Application for plugging approved July 9, 19 60  
Plugging commenced July 9, 19 60  
Plugging completed July 10, 19 60  
Reason for abandonment of well or producing formation Dry hole.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production ----- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot  
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 6350 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8/58	1377'	Left in cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Filled hole with heavy mud to 500 feet, and placed cement plug from 500 to 440 feet with 20 sacks cement and the sack bulbs through drill pipe. Filled hole with heavy mud to 65' set cement plug from 65' to 35' with 10 sacks cement and 1/2 sack hulls. Top of plug of 35'. Capped well on top of plug with 10 sacks cement. All cement pumped through drill pipe

RECEIVED  
STATE CORPORATION COMMISSION

AUG 16 1960 8-16-60

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Panhandle Development Co., Inc.  
Address Box 457, Liberal, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack R. Warkentin  
Box 457 Liberal, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 60

My commission expires June 8, 1964  
Elizabeth M. Smith  
Notary Public.



15-119-00120-0000

PANHANDLE DEVELOPMENT CO., INC.  
BOX 457  
LIBERAL, KANSAS

Panhandle Development Co., Inc.  
Gage #1  
C NE NE 6-34S-30W  
Meade County, Kansas

Sand and gravel	0-550
Red beds & shells	550-925
Sand	925-1070
Red beds and sand	1070-1385
Red beds and anhydrite	1385-2071
Anhydrite & shales	2071-2455
Lime and shale	2455-2665
Lime	2665-2755
Lime and shale	2755-2985
Lime	2985-3132
Lime and shale	3132-4034
Shale and lime	4034-4400
Lime and shale	4400-4500
Lime	4500-4658
Lime and shale	4658-4723
Lime with thin shale zones	4723-5220
Lime with thin shale streaks	5220-5370
Lime	5370-5544
Shale with lime stringers	5544-5700
Shale	5700-5729
Shale and sand	5729-5770
Shale and lime stringers	5770-5800
Lime with shale stringers	5800-5902
Lime and shale	5902-6065
Lime with very thin shale stringers	6065-6350

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1960  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify that this is a complete drillers log of the above described well as taken from our daily drilling reports.

PANHANDLE DEVELOPMENT CO., INC.

By Jack S. Wharton

Subscribed and sworn to before me this 9th day of August, 1960.

Elizabeth M. Smith  
Notary Public

My commission expires January 5, 1964