


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Meade County, Sec. 6 Twp. 34S Rge. (E) 30 (W)
Location as "NE/CNW&SW&" or footage from lines C NW NW
Lease Owner William Gruenerwald & Associates
Lease Name Fox Well No. 2
Office Address Box 909, Colorado Springs, Colorado 80901
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 1963
Application for plugging filed November 4, 1967
Application for plugging approved November 7, 1967
Plugging commenced November 7, 1967
Plugging completed November 10, 1967
Reason for abandonment of well or producing formation Non commercial gas well

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1436	None
				5 1/2"	5998	2620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mix 25 sacks of cement and 1 sack hulls to plug off perforations at 5627 feet. Stop plug at 5500 feet. Pump 35 sacks of cement at 650 feet to 550 feet. Put 10 sacks of cement at 40 feet to @.


RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent's Casing Pulling Service
Address P. O. Box 506, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEWARD, ss.
Robert Sargent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Sargent
Box 506, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1968
Mona M. Clark
Notary Public.



15-119-10250-0000

6-34-30W

WILLIAM GRUENERWALD & ASSOCIATES

BOYD FOX #2
Meade County, Kansas

COMMENCED OPERATIONS: 7-15-63
COMPLETED OPERATIONS: 8- 6-63

DRILLERS LOG

0 - 581	Sand and Shells
581 - 1202	Gypsum, Sand and Shell
1202 - 1436	Shale, Gypsum and Anhydrite
1436 - 2295	Shale and Anhydrite
2295 - 2675	Anhydrite and Lime
2675 - 2881	Lime and Dolomite
2881 - 2941	Shale, Anhydrite and Lime
2941 - 3099	Lime and Anhydrite
3099 - 3641	Chalky Lime and Lime
3641 - 3696	Lime
3696 - 4488	Lime and Shale
4488 - 4716	Lime
4716 - 5127	Shale and Lime
5127 - 5169	Lime
5169 - 5225	Lime and Shale
5225 - 5375	Lime
5375 - 5717	Lime and Shale
5717 - 5767	Lime and Sand
5767 - 5805	Lime and Shale
5805 - 5898	Lime
5898 - 5940	Lime and Shale
5940 - 6000	Lime

CASING RECORD

7-18-63

Run 46 Jts. 8 5/8" 24# casing.
Set @ 1436' K.B.M. cemented
w/500 Pozmix 2% gel. added and
200 com. 2% c.c.

8-6-63

Ran 180 Jts. 5 1/2" casing set
@ 5953' K.B.M. cemented w/100
sacks pozmix.