

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-119-20, 011-0000

LEASE NAME H. G. Adams

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-28

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 28 TWP. 34S RGE. 29 (S) or (W)

COUNTY Meade

Date Well Completed 11-16-67

Plugging Commenced 6-28-89

Plugging Completed 7-01-89

LEASE OPERATOR Kaiser-Francis Oil Co.

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/8/89 (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Chester Depth to Top 5936 Bottom 6006 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Chester</u>	<u>gas</u>	<u>5936</u>	<u>6006</u>	<u>9 5/8"</u>	<u>1,374'</u>	<u>NONE</u>
				<u>4 1/2"</u>	<u>6,100'</u>	<u>2,456.90'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CTBP 5,900' with 15' cement on top 30 sack cement stub plug from 2309'-2209'.
50 sack cement plug from 1,425' to 1,325'
25 sack cement plug from 650' to 600'
10 sack cement plug from 40' to 4'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves Casing License No. 3003

Address P. O. Box 94204, Oklahoma City, Oklahoma 73143

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Co.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and a true and correct copy of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
 JUL 31 1989
 (Signature) C. Jan Valkenburg
 (Address) P.O. Box 21468, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 89
 Conservation Division
 Wichita, Kansas

Brenda Bowdler
 Notary Public

My Commission Expires: June 27, 1990