


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 33 Twp. 28S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines. C NW NE SE
Lease Owner. Rains & Williamson Oil Co.
Lease Name. CARVER-PAINE Well No. 1
Office Address. 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 26 19 65
Application for plugging filed September 26 19 65
Application for plugging approved September 26 19 65
Plugging commenced September 26 19 65
Plugging completed September 26 19 65
Reason for abandonment of well or producing formation. No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4528 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	372.23'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 300', cemented thru drill pipe with 25 sacks cement. Mud back to 40', set solid bridge with plug and hulls, capped with 10 sacks cement and 2 sacks cement in rathole. Plug down 3:05 a.m. 9-26-65.

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 65

My commission expires January 8, 1968
Shirley Keck Notary Public.

ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.
#1 Carver-Paine
C NW NE SE Section 33-28S-12W
Pratt County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.
COMMENCED: 9-13-65
COMPLETED: 9-26-65
REMARKS: Set 372.23' of 8-5/8"
Surface Casing with
225 sacks GL3 cement.

FORMATIONS:

Clay & Shale	65'
Sand	270'
Red Bed & Sand	340'
Red Bed	680'
Anhydrite	730'
Shale & Shells	860'
Shale & Lime Streaks	1530'
Shale & Lime	1905'
Lime & Shale	2930'
Shale & Lime	3070'
Lime & Shale	3795'
Lime	4225'
Lime & Shale	4250'
Lime & Chert	4309'
Lime & Shale	4420'
Lime & Chert	4498'
Sand	4528'
RTD (D & A	4528'

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

CONSERVATION DIVISION
Topeka, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State
of Kansas, County of Sedgwick, this 29th day of September, 1965.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public