

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-30092-0001

LEASE NAME JOHANNSSEN BARBY

WELL NUMBER 1

SPOT LOCATION C SE NW

SEC. 32 TWP. 34S RGE. 27 (~~XXXX~~(W))

COUNTY MEADE

Date Well Completed 9-12-74

Plugging Commenced 6-12-84

Plugging Completed 6-14-84

LEASE OPERATOR KAISER-FRANCIS OIL COMPANY

ADDRESS P.O. BOX 21468

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well GAS
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT 1, DODGE CITY, KANSAS

Is ACO-1 filed? YES If not, is well log attached? --

Producing formation COUNCIL GROVE Depth to top 3051 bottom 4463 T.D. 6310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHESTER MISSISSIPPI	GAS	6051	6625	8 5/8	1238	-0-
COUNCIL GROVE	GAS	3051	4463	2 7/8	6309	2259

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. SET BP @ 6,150'. SET CIBP @ 6030'. DUMP 10' CMT ON TOP TO 6020'. PUMPED 5 SX CMT PLUG TO PERFS. SHOT 2 7/8" TBG & LD 2259'. SPOT 35 SX PLUG FROM 1250-1150'. SPOT 35 SX CMT PLUG FROM 650-550'. SPOT 10 SX CMT PLUG FROM 40-3'. CUT OFF WELL HEAD & WELD ON PLATE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CSG. PULLING SERVICE License No. 6497
Address BOX F, SUBLETTE, KANSAS 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

JUN 21 1984

Drew Tyler DREW TYLER, ENGINEER (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Drew Tyler

(Address) P.O. BOX 21468, TULSA, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 19th day of JUNE, 19 84

Sue Mills
Notary Public

My Commission expires: 10-4-87

SUE MILLS