


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Meade County, Sec. 32 Twp. 24³⁴-S. Rge. (E) 27(W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Apache Corporation
Lease Name Johanssen-Barby Unit Well No. 1
Office Address 823 South Detroit, Tulsa, Oklahoma 74120
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed July 19 1966
Application for plugging filed August 3 1966
Application for plugging approved -- 19
Plugging commenced July 19 1966
Plugging completed July 19 1966
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production No production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ed. Avers
Producing formation None Depth to top Bottom Total Depth of Well 6797 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Water	3051		8-5/8	1237.09	None
Toronto	-	4504				
Lansing	-	4632				
Morrow	N.S.	6006				
Chester	Water	6051				
St. Louis	N.S.	6626				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud-laden fluid through drill pipe using rotary mud pump and placed 50 sacks of cement in 8-5/8" OD at 600 to 750', and capped 8-5/8" with 15 sacks cement 0 to 50'. Cut off 8-5/8" at least 3' below ground level.

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lohmann-Johnson Drilling Company, Inc.
Address 320 Indiana Bank Building, Evansville, Indiana

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Lloyd D. Somers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd D. Somers x
823 South Detroit, Tulsa, Oklahoma 74120
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1966

My commission expires November 20, 1969.
Letha M. Douglas Notary Public.

WELL RECORD

Apache Corporation, owner

Johannsen-Barby Unit, Well No. 1SE NW Sec 32-T24S-R27W
Meade County, Kansas

Spudded: June 30, 1966

Elevation: 2329' GL

Completed: July 9, 1966

Casing: 8-5/8" OD 28# ST&C
set at 1237.09'.

Cement: 750 sacks

Formation:

Depth:

Sand and shale	0 - 1063
Red beds	1063 - 1597
Anhydrite and shale	1597 - 1675
Shale and sand	1675 - 2027
Shale and lime	2027 - 2628
Lime	2628 - 2956
Lime and shale	2956 - 3870
Shale	3870 - 4348
Lime and shale	4348 - 4814
Lime	4814 - 5906
Lime and sand	5906 - 6022
Lime	6022 - 6797

Total Depth:

6797'

Tops: Council Grove 3051'
Toronto 4504'
Lansing 4632'
Morrow 6006'
Chester 6051'
St. Louis 6626'

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1966

CONSERVATION DIVISION
Wichita, Kansas

State of Oklahoma)
County of Tulsa) Ss.

I hereby certify that the above information is true and correct
to the best of my knowledge and belief.

Lloyd O. Somers
Division Production Superintendent

Subscribed and sworn to before me this 3rd day of August, 1966.

My commission expires
November 20, 1969.

Leta M. Daugherty
Notary Public