

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER N/A

LEASE NAME Johannsen

WELL NUMBER #1

SPOT LOCATION NE SW

SEC. 29 TWP. 34S RGE. 27W (E) OR (W)

COUNTY Meade

DATE WELL COMPLETED 7-20-67

PLUGGING COMMENCED 8-23-83

PLUGGING COMPLETED 8-25-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Natomas North America, Inc.

ADDRESS 1 West Third St., Suite 900, Tulsa, OK 74103

PHONE #(918) 582-1581 OPERATORS LICENSE NO. 7626

CHARACTER OF WELL Gas  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita Kansas

Is ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION Chester DEPTH TO TOP 6011' BOTTOM 6025' T.D. 6750'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Chester	Gas	6011'	6025'	8 5/8	1224	-0-
				4 1/2	6248	4518

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. 8-23-83  
8-23-83 The hole was circulated with 9.5 mud through the tubing. 8-23-83 Set CIBP at 5990 ft. 2 sx cement on top, Cut pipe off at 4518 ft, pulled to the bottom of surface. Pumped 60 sx cement plug on 8-25-83 from 1165 to 1285 ft. 8-25-83 Pulled csg. up and pumped a 25 sx cement plug from 450 to 500 ft. Capped 8 5/8 surface with 10 sx cement circulating it from 4 to 44 ft. 8-25-83 Welded steel plate with name and date on top.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin Casing Pulling, Inc. LICENSE NO. 8733  
ADDRESS P.O. Box 389, Enid, Oklahoma 73702

STATE OF Oklahoma COUNTY OF Tulsa, SS.

Craig Conrad (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Craig Conrad  
Craig Conrad  
(SADDRESS) Suite 900, 1 West Third Street  
Tulsa, Oklahoma 74103

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th DAY OF September, 1983

Kelly L. Watson  
NOTARY PUBLIC

MY COMMISSION EXPIRES: July 10, 1985

RECEIVED  
STATE CORPORATION COMMISSION  
FORM CP-4  
REVISED 06-83

SEP 12 1983

CONSERVATION DIVISION  
Wichita, Kansas