

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-103010000

LEASE NAME Geo. Merkle

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 14 TWP. 34 SRGE. 27 W (E) or (W)

COUNTY Meade

Date Well Completed 1-6-73

Plugging Commenced 10-22-91

Plugging Completed 10-24-91

LEASE OPERATOR Bentley & Lainy

ADDRESS P.O. Box 294 Wichita Falls, Texas 76307

PHONE#(817) 723-5001 OPERATORS LICENSE NO. 9183

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-22-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Chester-Mississippi Depth to Top 6042 Bottom 6072 T.D. 6140

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Chester-Mississippian	Gas	6042	6072	8 5/8	1390	0
				5 1/2	6140	3023

DEC 02 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 25 sks. of cement & 1 sk. of hulls from 6074 to 5900

Pump 50 sks. of cement from 1430 to 1330

Pump 40 sks. of cement from 625 to 525

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bentley & Lainy

STATE OF Texas COUNTY OF Wichita, ss.

Doyle Bentley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Doyle Bentley*

(Address) Box 294, Wichita Falls, TX 76307

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 91

Eileen P. Newman
Notary Public

My Commission Expires: 5/7/94