

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20,638-0000 (of this well) 8/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) LOFLAND "A" WELL NO. 1 WELL LOCATION C SE/4 COUNTY Seward

SEC. 6 TWP. 35S RGE. 31 or (W) TOTAL DEPTH 6590' PLUG BACK TD 5420'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1653' CEMENTED WITH 750 SACKS

CASING SIZE 4-1/2" SET AT 6110' CEMENTED WITH 300 SACKS

PERFORATED AT 5380-5390'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 50' cmt plug above perms (5380-5390'). Find
freepoint and salvage 4-1/2" csg, 50' cmt plug across csg cut, 100' cmt plug at surface csg
depth, 50' cmt plug at 600', 40' cmt plug to surface and cap casing 3' below ground level.

(If additional space is needed use back of form)

Driller's Log

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? attached IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. A. Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67901 STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 JAN 28 1987 6/87

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455 CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease

(Operator or Agent)

M. L. Pease, Division Production Manager

DATE: 1/26/87

①

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

ENDS 2 '87

EXPIRES

February 2, 1987

WELL PLUGGING NOTICE

Lofland "A" #1
C SE/4
Sec. 06-35S-31W
Seward County

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in black ink, appearing to read "Jack McCord".

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760
five days prior to plugging the well (KAR-82-3-113).