

To: V 1 020634 12-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,859-00-00 1178
C SW NW, SEC. 16, T 34 S, R 28 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011
Operator: Viking Resources, Inc.
Name & Address 105 S. Broadway, Ste. 1040
Wichita, KS 67202

3300 feet from S section line
4620 feet from E section line
Lease Name Enns Well # 1
County Meade
Well Total Depth 6419 208.62 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1595

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 23 Month: 12 Year: 1992

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

work: 5 1/2" at 3270' w/225 sx cement, PBSD 3260', Perfs at 3000-02, 3022-24, 3043-45'
1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud,
2nd plug pump 35 sx cement at 2128', 3rd plug pump 40 sx cement at 1600',
4th plug pump 35 sx cement at 700',
5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:30 p.m. Day: 29 Month: 12 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced
with mud,
2nd plug pumped 35 sx cement at 2128',
3rd plug pumped 40 sx cement at 1600',
4th plug pumped 35 sx cement at 700',
5th plug pumped 10 sx cement at 40 to -4'. Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2128' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 1-19-93

INV. NO. 39214

FEB 24 1993

Signed Glenn Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
1-4-93
4 1993