

1070135

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,833-00-00
50'W NE/4 NE/4 SEC. 15, T 34 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 710 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ENNS "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 210.15

OPERATOR LICENSE # 6113

WELL TOTAL DEPTH 6466 FEET

OPERATOR: LANDMARK ENERGY EXPLORATION PRODUCTION CSG: SIZE 5 1/2" @ 3454' WITH 100 SX

NAME AND 1861 N ROCK ROAD, SUITE 205 SURFACE CASING: SIZE 8 5/8" @ 628' WITH 330 SX

ADDRESS WICHITA, KS 67206

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 12:25 PM DAY: 07 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM LARRY DREILING

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 3098-3100, CIBP @ 3126, PEFS AT 3138-42, CIBP @ 3164, PEFS AT 3168-70, 3260-62, CIBP @3273.

BOTTOM PLUG PUMP 200# HULLS AND 25 SX CEMENT. PUMP 25 SX GEL. GEL SPACER TO 1300'. PUMP 72 SX CEMENT TO SURFACE. MAXIMUM PSI @ 1600#. SHUT IN AT 1300#. TIE ONTO 8 5/8 X 5 1/2 ANNULUS PUMP 85 SX CEMENT 676' TO SURFACE. MAXIMUM PRESSURE 500#. SHUT IN AT 350#.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

RECEIVED
STATE CORPORATION COMMISSION

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 07 MONTH: 06 YEAR: 2000 JUN 12 2000

ACTUAL PLUGGING REPORT _____

CONSERVATION DIVISION
Wichita, Kansas

BOTTOM PLUG PUMP 200# HULLS AND 25 SX CEMENT. PUMP 25 SX GEL. GEL SPACER TO 1300'. PUMP 72 SX CEMENT TO SURFACE. MAXIMUM PRESSURE 1600#. SHUT IN WITH 1300#. TIE ONTO 8 5/8 X 5 1/2 ANNULUS. PUMP 85 SX CEMENT 676' TO SURFACE. MAXIMUM PRESSURE 500#. SHUT IN WITH 350#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 6/14/00
WV. NO. 61864

SIGNED

[Signature]
(TECHNICIAN)

FORM CP-2/3

[Signature]