

1090990

20874-0000

TO: STATE CORPORATION COMMISSION

3-24

API NUMBER 15-119-~~0000~~
SE SE SW SEC. 15, T 34 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MEIERDIERKS WELL # 2-15

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 170.34

OPERATOR LICENSE # 30129 WELL TOTAL DEPTH 5241 FEET

OPERATOR: EAGLE CREEK CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4962' WITH 125 SX

NAME AND 107 N MARKET, SUITE 509 SURFACE CASING: SIZE 8 5/8" @ 1225' WITH 550 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CASING PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 24 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SARGENTS CASING PULLING (PHONE) 316-624-7455

WERE: PERFS AT 4860-90

1ST PLUG 1 HULL AND 25 SX CEMENT OVER PERFORATIONS. 2ND PLUG PULL CASING TO 1250'.

LOAD HOLE WITH MUD SPOT 50 SX CEMENT. 3RD PLUG PULL TO 600'. SPOT 40 SX CEMENT.

4TH PLUG PULL TO 40'. CIRCULATE 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:40 PM DAY: 24 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 1 HULL AND 25 SX CEMENT OVER PERFORATIONS.

2ND PLUG PULL CASING TO 1250'. LOAD HOLE WITH MUD. SPOT 50 SX CEMENT.

3RD PLUG PULL CASING TO 600'. SPOT 40 SX CEMENT.

4TH PLUG PULL CASING TO 40'. CIRCULATE 10 SX CEMENT. HOLE STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1999
3-29-99
CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2450' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) 4-2-99 OBSERVE THIS PLUGGING.

DATE

SIGNED (TECHNICIAN)

FORM CP-2/3

INV. NO. 60764