

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20465-00-00

R

Sus. Well Sec. 15, T 34 S, R 28 W1/4

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name Murdierka Well #1-15

Operator: Mesa Petroleum Co.
Name & Address P.O. Box 18950
Oklahoma City, OK
73154

County Meade

Well Total Depth 5975 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 1496

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike Proctor Casing Pulling License Number 6418

Address Ste. 417, 3022 NW Expressway, Oklahoma City, OK 73112

Company to plug at: Hour: 8:00 AM, Day: 10 Month: Jan Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Charles Behrens

(company name) Proctor (phone) _____

were: Cement the bottom w/25 sp. cmt to 2900'. Shoot off casing and spot 25 sp. cmt @ free point. Locate plugs @ 1620' w/40 sp. cmt; 780' w/25 sp. cmt and 40-0' w/10 sp. cmt.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 p.m., Day: 11 Month: JAN Year: 19 83

ACTUAL PLUGGING REPORT plugged as ordered.

Remarks: 4 1/2" casing @ 3163' - Perfs @ 2966-74 & 2980-95
PBTD @ 3005' w/cast iron bridge plug.
Recovered 1605' of 4 1/2"

I hereby certify that the above plugging instructions were given as herein stated and that I (~~was~~ / did not) observe this plugging.

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE 1-25-83

Signed R. Barluttan
(TECHNICIAN)

INV. NO. 2225-W

JAN 18 1983

FORM CP-2/3
Rev. 9-82

CONSERVATION DIVISION
Wichita, Kansas