

To: 1 090428
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-24

API NUMBER 15-119-20,864-00-00

100' E 66 S/2 NW, SEC. 15, T. 34 S, R. 28 W

1980 feet from N E section line

1420 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Operator: Charter Production Company

Name & Address 142 N. Mosley

Wichita, KS 67202

Lease Name Evans Well # 1

County Meade 109.20

Well Total Depth 3360 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 635

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1 p.m. Day: 24 Month: 5 Year: 19 94

Plugging proposal received from Bob Moorehead

(company name) Pratt Well Service (phone) 316-672-2531

logs: 4 1/2" at 3350' w/150 sx cement. PBD 3225', Perfs at 3197-98', 3215-17'

1st plug set CIBP at 3150' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 24 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3150' and dump 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure: 700 psi and shut in 500 psi.

RECEIVED STATE CORPORATION COMMISSION

MAY 26 1994

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2178' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

MAY 31 1994

observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE _____

INV. NO. 40507

5-24