

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20861-00-00
Spot: CN2SW Sec/Twnshp/Rge: 14-34S-28W
1980 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: DAVIS Well Number: 2-14
County: MEADE Total Vertical Depth: 3130 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 107 NORTH MARKET, #509
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 1538 WITH 590 SX CMT
Production: Size 4.5 feet: 3100 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/06/2001 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS OVER PERFS. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/06/2001 5:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 3053'. PERFS AT 2913-2917'. PUMP 20 SX CMT & 200# HULLS OVER PERFS. LOAD HOLE WITH MUD. 1ST PLUG PULL TO 1560' & SPOT 50 SX CMT. 2ND PLUG PULL TO 600' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 2650' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

DEC 07 2001

RECEIVED
12-17-01
DEC 17 2001

KCC WICHITA

INVOICED

DEC 06 2001

DATE 12-19-01 MP

INV. NO. 2002061077

Form 11/23

