

1 020205

1-31

255 / R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,783 -06-00
E/2 NE NW, SEC. 13, T 34 S, R 28 W/XX

4620 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Lease Name Davis Well # 1-13

Operator: Ensign Operating Company
Name & Address: 621 17th Street, Suite 1800
Denver, CO 80293

County Meade 196.63

Well Total Depth 6050 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1510

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 31 Month: 1 Year: 19 89

Plugging proposal received from Reed Wacker

(company name) H-30 Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1480-1510'

1st plug at 1540' with 50 sx cement, 2nd plug at 720' with 20 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 a.m. Day: 31 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement,

2nd plug at 720' with 20 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-2-89
FEB 2 1989

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

Signed Glenn R. Barber (TECHNICIAN)

DATE 2-7-89

INV. NO. 23877
1-31

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date, 01 20 89 month day year

API Number 15- 119 - 20,783

OPERATOR: License # 04782 Name Ensign Operating Co. Address 621 - 17th Street, Suite 1800 City/State/Zip Denver, CO 80293 Contact Person L. T. Hartnett Phone 303/293-9999

C E/2 NE NW Sec. 13 Twp. 34 S, Rg. 28 4620' 2970'

CONTRACTOR: License # 5107 Name H-30 Inc. City/State Wichita, KS 67202

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 660 feet County Meade

Well Drilled For: X Oil Storage Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Lease Name Davis Well # 1-13 Ground surface elevation 2289' feet MSI

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Domestic well within 330 feet: Municipal well within one mile: Depth to bottom of fresh water 250' 400' Depth to bottom of usable water 500'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 1/11/89 Signature of Operator or Agent L. T. Hartnett Title Manager, Operations

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 1550' Conductor pipe required N/A Projected Total Depth 6050' feet Formation Chester

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 520' feet per Alt. 1 X This Authorization Expires 1-13-89 Approved By LTM 1-13-89

EFFECTIVE DATE: 1-18-89 Set 1550' of 8 3/8 on 1-20-89

C E/2 NE NW Sec. 13 Twp. 34 S, Rg. 28 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 1550' or formation with 100' feet of 60/40 Pozmix
2nd plug @ ft. deep 700' or formation with 100' feet of 60/40 Pozmix
3rd plug @ ft. deep 40' to surface or formation with 40' feet of 60/40 Pozmix
4th plug @ ft. deep or formation with feet of
5th plug @ ft. deep or formation with feet of

(2) Rathole to surface minus 5 feet 15 SXS (b) Mousehole to surface minus 5 feet, 10 SXS

55-114
PUSHER Reed Wacker
TD 6050 FORMATION
SURFACE PIPE 8 3/8 @ 1510
ANHYDRITE 1 5/8 ELEVATION 2282
STARTING TIME & DATE 100 AM 1-31-89
COMPLETION TIME & DATE 530 AM 1-31-89
1st PLUG @ 1540 FT. W/ 5-0 SX
2nd PLUG @ 720 FT. W/ 2-0 SX
3rd PLUG @ 40-0 FT. W/ 1-0 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 1 5/8 in SX
MOUSE HOLE CIRCULATED W/ 1-0 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Hall
P.L. S. TECHNICIAN

60/40 w/ 6% gel

RECEIVED STATE CORPORATION COMMISSION FEB 2 1989 CONSERVATION DIVISION Wichita, Kansas