

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20151-00-00  
Spot: NWSWSEW Sec/Twnshp/Rge: 24-34S-28W  
2000 feet from N Section Line, 1500 feet from W Section Line  
Lease/Unit Name: DAVIS Well Number: 1-24  
County: MEADE Total Vertical Depth: 6250 feet

Operator License No.: 30129  
Op Name: EAGLE CREEK CORPORATION  
Address: 107 NORTH MARKET, #509  
WICHITA, KS 67202

Conductor Pipe: Size feet: 203.13  
Surface Casing: Size 8.625 feet: 900 WITH 700 SX CMT  
Production: Size 4.5 feet: 6250 WITH 100 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/17/2001 9:30 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Revd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS ON BOTTOM. 1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 920' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/17/2001 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6205'. PERFS AT 6054-66'. PUMP 200# HULLS WITH 25 SX CMT FOR BOTTOM PLUG ON 12/13/01. 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 1430'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH 23 BBL MUD. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2" TO 920'. PUMP 50 SX CMT. DISPLACE WITH 15 BBL MUD. 3RD PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 40'. LOAD HOLE WITH MUD. PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 2640' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PERTTE  
(TECHNICIAN)

RECEIVED

DEC 31 2001

KCC WICHITA

INVOICED

DATE 01-02-02

INV. NO. 2002061113

DEC 26 2001

Form CR-23

MP