

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-063-21149-00-00

LEASE NAME Foos

WELL NUMBER "N" #1

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC 26 TWP. 14 RGE. 29 (E) or (W)

COUNTY Gove

Date Well Completed _____

Plugging Commenced 10-24-87

Plugging Completed 11-6-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS Box 1303, Great Bend, Kansas 67530

PHONE# (316)-792-2802 OPERATORS LICENSE NO. 5123

Character of Well Oil DH *KCC*

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Six (6)

Is AGO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	300'	None
				4-1/2"	4373'	1,292.16'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3700' and 4 sacks cement. Shot casing at 3600', 3300', 2900', 2500', 2000', 1300' and 1250'. Pulled 31 joints of 4-1/2" casing. Allied squeezed well with 3 sacks hulls and 200 sacks ATL cement blended with 2 sacks hulls. Maximum pressure was 600 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 87

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public

My Commission Expires:

NOV 9 1987