

1 060467

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,695-00-00  
C NE \_\_\_\_\_, SEC. 18, T 34 S, R 28 W/EX

3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name McGuire 'J' Well # 1

Operator: Petroleum, Inc.  
Name & Address 300 West Douglas, Suite 800  
Wichita, KS 67202

County Meade 211.58

Well Total Depth 6510 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1635 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rine Drilling Company License Number 6059

Address 300 West Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 14 Month: January Year: 19 85

Plugging proposal received from Steve Phillips

(company name) Petroleum, Inc. (phone) 316-624-1686'

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1650' with 50 sx cement

2nd plug at 810' with 25 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luttie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8:00 pm Day: 14 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 810' with  
25 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to  
circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
1-23-85  
JAN 23 1985

Plugging orders given by Steve Durrant

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

(I (did / observe) observe this plugging.

Signed Paul A. Luttie SO  
(TECHNICIAN)

FILE NO. 6659