

To: 1020883 7-7  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,899-0001  
SW NE SE, SEC. 22, T 34 S, R 30 W/E  
1650 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31581  
Operator: Merex Resources, Inc.  
Name & Address: P.O. Box 50955  
Amarillo, TX 79159

Lease Name Adams Well # 1-22  
County Meade  
Well Total Depth 6602 214.57 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1514

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H & K Plugging & Salvage License Number 31705

Address: \_\_\_\_\_

Company to plug at: Hour: 3:30 p.m. Day: 7 Month: 7 Year: 1995

Plugging proposal received from Dennis Holman

(company name) H & K Plugging & Salvage (phone) 806-665-2550

were: 4 1/2" at 5435' w/100 sx cement, PBSD 3715'; Perfs at 3187-3710'

1st plug set CIBP at 3100' with 2 sx cement on top,

2nd plug pump 50 sx cement at 1530'

3rd plug pump 40 sx cement at 600'

4th plug pump 10 sx cement at 40'

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8 p.m. Day: 7 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3130' with 2 sx cement on top,

2nd plug pumped 50 sx cement at 1550'

3rd plug pumped 40 sx cement at 600'

4th plug pumped 10 sx cement at 40-0'

Gel mud between all plugs.

Remarks: Used common cement by H & K Plugging & Salvage. Recovered 2544' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(If you observe this plugging.)

DATE 7-18-95

INV. NO. 43104

7-7

NOV 02 1995

Signed Glenn R. Barlow (TECHNICIAN)

