

1060166

8-5

TO: STATE CORPORATION COMMISSION 55'N 57'E NW SE SE SEC. 21, T 34 S, R 30 W API NUMBER 15-119-21,002-0000

CONSERVATION DIVISION - PLUGGING SECTION 1045 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1047 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HARDEN FARMS WELL # 1-21

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE

OPERATOR LICENSE # 30604 WELL TOTAL DEPTH 6280 FEET

OPERATOR: RAYDON EXPLORATION, INC PRODUCTION CSG: SIZE " FEET

NAME AND ADDRESS 9400 N BROADWAY, SUITE 400 SURFACE CASING: SIZE 8 5/8" @ 1620' WITH SX

OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856

COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 05 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GILBERT

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE:

1ST PLUG AT 1640' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 300' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:00 AM DAY: 05 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1640' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 300' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

AUG 30 1999 8-30-99 CONSERVATION DIVISION WICHITA, KANSAS

REMARKS: USED 60/40 POZMIX 6% GEL BY DOWELL.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

INDENTED NOT OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN)

FORM CP-2/3

DATE 8-31-99

INV. NO. 60450

Handwritten initials and a circled 'R'.