

To: 1 020489 8-15  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9262

Operator: Lowry Exploration, Inc.

Name & Address P.O. Box 1847

Liberal, KS 67905-1847

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3:30 p.m. Day: 13 Month: 8 Year: 19 92

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5899' w/200 sx cement, PBTD 5885', Perfs at 5730-5804'

1st plug pump 2 sx hulls and 20 sx cement at perfs, pressure up,

2nd plug pump 50 sx cement at 1450',

3rd plug pump 25 sx cement at 700',

4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☒ None ☐

Operations Completed: Hour: 3 p.m. Day: 15 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs, pressured to

400#. Top of cement 5600'. Displaced with mud,

2nd plug pumped 50 sx cement at 1450',

3rd plug pumped 25 sx cement at 700',

4th plug pumped 10 sx cement at 40 to -4'.

All plugs displaced with mud.

Remarks: Used common cement by Sargent's. Recovered 2814' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (old / ~~XXXXXX~~) observe this plugging.

DATE 9-14-92

INV. NO. 36139

API NUMBER 15- 175-20,455-00-00

NE NE NE, SEC. 21, T. 34 S, R 31 W/E

4950 feet from S section line

330 feet from E section line

Lease Name Langhofer Well # 1

County Seward 191.75

Well Total Depth 5900 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1453

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1992

CONSERVATION DIVISION  
Wichita, Kansas

Signed Glenn R Barlow  
(TECHNICIAN)