

1 080594

1-22-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,924-0000

S/2 SW NW SEC. 2, T 34 S, R 31 (W/E)
2970 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3145

Lease Name Gene Black Well # 1A

Operator: Jorford Corporation
Name & Address 1212 13th Street, Suite 200
Lubbock, TX 79401

County Seward 199.88

Well Total Depth 6150 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1562

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 22 Month: 1 Year: 1987

Plugging proposal received from Ronny Madison

(company name) Sage Drilling Company (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2720'

1st plug at 3000' with 125 sx cement, 2nd plug at 1590' with 50 sx cement,

3rd plug at 660' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement;

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11 p.m. Day: 22 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3000' with 125 sx cement,

2nd plug at 1590' with 50 sx cement,

3rd plug at 660' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 50/50 Pozmix by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

1-29-87
JAN 28 1987

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Signed J.A. [Signature] (TECHNICIAN)

DATE 1-29-87

INV. NO. 16015

1-22

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 1, 1986

API Number 15-175-20,924-0000
S. 1/2 SW. NW. Sec. 2 Twp. 34 S. Rg. 31 East
2970 Ft. from South Line of Section
4620 Ft. from East Line of Section

OPERATOR: License # 3145
Name Jorford Corporation
Address 1212 - 13th Street, Suite 200
City/State/Zip Lubbock, TX 79401
Contact Person Larry Langerhans
Phone 806-763-7831

Nearest lease or unit boundary line 660 feet
County Seward
Lease Name Gene Black Well # 1A
Ground surface elevation 2720 (est) feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Surface pipe by Alternate: 1 2
Depth to bottom of fresh water 620
Depth to bottom of usable water 650
Surface pipe planned to be set 1600
Projected Total Depth 6200 feet
Formation Mississippi

CONTRACTOR: License # 5421
Name Sage Drilling Co.
City/State Wichita, KS 67202

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-28-86 Signature Casey Coats Title Petroleum Engineer

For KCC Use:
Conductor Pipe Required feet: Minimum Surface Pipe Required 700 feet per Al
This Authorization Expires 5-21-87 Approved By

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug #, Group, Depth (feet), and SXS of. Includes rows for 1st through 5th plugs and Rathole/Mousehole.

PUSHER Ranni Morrison
TD 1150 FORMATION MISSISSIPPI
SURFACE PIPE 8 3/4 @ 1562
ANHYDRITE ELEVATION 2720
STARTING TIME & DATE 11:00 AM - 1-22-87
COMPLETION TIME & DATE 11:00 AM - 1-27-87
1st PLUG @ 3000 FT. WI 125 SX
2nd PLUG @ 1940 FT. WI 50 SX
3rd PLUG @ 660 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI SX
CEMENT COMPANY Halliburton
TECHNICIAN

STATE CORPORATION COMMISSION
JAN 28 1987
CONSERVATION DIVISION
Wichita, Kansas