

To: 1 020439
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,924-0001 22
2-10 S/2 SW NW, SEC. 2, T. 34 S, R. 31 W/EX
2970 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3170
Operator: Shannon Energy Corporation
Name & Address P.O. Box 6026
Liberal, KS 67905-6026

Lease Name Black Well # 2-1
County Seward 199.87
Well Total Depth 6150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1562

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 7 Month: 2 Year: 1992

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5290', PBTD 5239', Perfs at 5131-37'
1st plug pump 1 sx hulls and 20 sx cement to 5000',
2nd plug pump 50 sx cement at 1562',
3rd plug pump 35' sx cement at 600',
4th plug pump 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Glenn B. Barber 2-12-92

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 10 Month: 2 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, pressured up,
displaced with mud,
2nd plug shot pipe at 2835', loaded hole with mud, pumped 50 sx at 1580',
3rd plug pumped 35 sx cement at 600', displaced with mud,
4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2835' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Glenn B. Barber
(TECHNICIAN)

DATE MAR 10 1992

INV. NO. 34717
2-10