

15-175-10209-0000R

To: 1 060710
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
CNEW, SEC. 1, T 34 S, R 30 W1/2
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License 15153

Lease Name Jane Blackwell # B-1
County Leavenworth 192.11
Well Total Depth 5911 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 1250

Operator: Texaco Inc.
Name & Address Texaco Bldg. 21st & Lewis
Box 2420
Tulsa, Oklahoma 74102

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargant's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, Kansas 67901

Company to plug at: Hour: 9:00AM Day: 5 Month: November Year: 1985
Plugging proposal received from Doug Blair

(company name) Sargant's Casing Pulling (phone) 316-624-7455

were: 1st plug 2 sbp bulbs + 25 sbp cement to bottom
2nd plug @ 1280' w/ 50 sbp cement.
3rd plug @ 600' w/ 30 sbp cement.
4th plug @ 40' to 0' w/ 15 sbp cement.
5 1/2" was set @ 5911' w/ Perfs. from 4305' to 4422' & 5793' to 5888'

Plug back ID- 5894 Plugging Proposal Received by Paul A. Luttich
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00PM Day: 5 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sbp bulbs + 25 sbp cement to bottom. 2nd plug shot off pipe & pulled to 1280' pumped 30 sbp cement. 3rd plug pulled pipe to 600' pumped 30 sbp cement. 4th plug pulled pipe & made solid bridge @ 40' & pumped 15 sbp cement. The hole was filled w/ heavy mud before pumping each plug. Cement was pumped by Sargant's

Remarks: They re-cemented 2602' of 5 1/2" casing. They pumped Common Cement.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-85

INV. NO. 11344

(I did not) observe this plugging
STATE CORPORATION COMMISSION signed Paul A. Luttich
(TECHNICIAN)
11-9-85

DEC 16 1985 NOV 8 1985

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84