

To: 1 020019
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,620 - 0000
C NW SW, SEC. 1, T 34 S, R 31
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5421
Operator: Sage Drilling Co., Inc.
Name & Address: 202 S. St. Francis
Wichita, KS 67202

Lease Name Black Well # 3-1
County Seward 198.25
Well Total Depth 6100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1549

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 5:00 pm Day: 2 Month: May Year: 19 86

Plugging proposal received from Kirby Lillard
(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 6099' PBTD 5910' Perfs at 5686-92'; 5704-06'; 5710-13' (Morrow) Present;
past: 5953-62' below CIBP; 4330-40'; 4344-47' (Squeezed off)

Pump through 5 1/2" with mud between plugs
1st plug pump 2 sx hulls and 30 sx cement to bottom
2nd plug at 1580' with 50 sx cement
3rd plug at 700' with 50 sx cement
4th plug from 40' to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 pm Day: 7 Month: May Year: 19 86

ACTUAL PLUGGING REPORT CIBP at 5932' - 1st plug ran 2 sx hulls and 30 sx cement (5-2-86)
(5-5-86) tagged cement at 5478'. 2nd plug ran heavy mud and 50 sx cement at 1580' and 50 sx
cement at 750', 4th plug ran 10 sx at 35' to 4' below surface. Cut off and welded cap on.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1986

Remarks: Recovered 2800' 5 1/2" casing. Used common cement by Sargent's
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed *Richard W. Lacey*
(TECHNICIAN)

DATE MAY 20 1986
INV. NO. 13922
5-7