

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20095-00-00
Spot: CNWNE Sec/Twnshp/Rge: 36-34S-30W
660 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: ADAMS A & H Well Number: 3
County: MEADE Total Vertical Depth: 6302 feet

Operator License No.: 30288
Op Name: SPESS OIL COMPANY
Address: 200 S. BROADWAY
CLEVELAND, OK 74020

Conductor Pipe: Size feet: 8204.82
Surface Casing: Size 8.625 feet: 1336 WITH 600 SX CMT
Production: Size 5.5 feet: 6302 WITH 250 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/17/2002 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS FOR BOTTOM PLUG. PLUG AT 1360' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH CMT TO SURFACE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/17/2002 2:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5988'. PERFS AT 5864-5880'. PUMP 25 SX CMT & 200# HULLS FOR BOTTOM PLUG. LOAD HOLE WITH MUD. 1ST PLUG AT 1360' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG PULL TO 40'. CIRCULATE CMT TO SURFACE. STAYED FULL.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01


Signed



(TECHNICIAN)

RECEIVED
1-24-02
JAN 24 2002
KCC WICHITA

INVOICED

DATE Jan 25, 02 JAN 22 2002
WV. NO. 2002061303 


Form CP-2/3