

15-119-10339-0000

To: 1090480  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-22 API NUMBER 15-Drill Comp. date 10/30/59

NE NW SE, SEC. 35, T. 34 S, R. 30 W  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134  
Operator: Graham-Michaelis Corporation  
Name & Address: P.O. Box 247  
Wichita, KS 67201

Lease Name Adams D Well # 2  
County Meade  
Well Total Depth 5959 193.66 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1276

Abandoned Oil Well Gas Well X Input Well SWD Well O&A  
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547  
Address P.O. Box 506, Liberal, KS 67901-0506

Company to plug at: Hour: Day: 22 Month: 9 Year: 1994

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5959' w/125 sx cement, Perfs at 5906-09, 5879-84, 5836-37, 5847-51'

- 1st plug pump 25 sx cement and 2 sx hulls on bottom,
- 2nd plug pump 50 sx cement at 1300',
- 3rd plug pump 50 sx cement at 750',
- 4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Day: 22 Month: 9 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 2 sx hulls on bottom,  
2nd plug pumped 50 sx cement at 1300',  
3rd plug pumped 50 sx cement at 600',  
4th plug pumped 10 sx cement to top off.

RECEIVED STATE CORPORATION COMMISSION SEP 29 1994

Remarks: Used common cement by Sargent's, Recovered 2742' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 10-6-94  
INV. NO. 41326