

1031304
12-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
240 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,922-0000
SE SE NE, SEC. 32, T. 7 S. R. 30 X
2310 feet from NX section line
393 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9534

Operator: Giant Exploration & Production Co.
Name &
Address P.O. Box 2810
Farmington, NM 87499

Lease Name Adams Well # 32H
County Meade

Well Total Depth 6450 209.63 feet
Conductor Pipe: Size 20" feet 40
Surface Casing: Size 8 5/8" feet 1523

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor BEREDCO INC. License Number 5147

Address 401 E. Douglas, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 17 Month: 12 Year: 1994

Plugging proposal received from David Rice

(company name) Crown Consulting, Inc. (phone) 316-624-0156

vers: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1530' with 50 sx cement, 2nd plug at 600' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2 a.m. Day: 18 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1994

12-20-94
CONSERVATION DIVISION
WICHITA KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

~~XXXX~~ did not observe this plugging.

DATE 1-4-95

Signed Steve Durrant

(TECHNICIAN)

INV. NO. 41950

EFFECTIVE DATE: _____

DISTRICT # _____
SGA? Yes No

State of Kansas 15
NOTICE OF INTENTION TO DRILL 119-20, 922-0000 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

FORM MUST BE TYPED
FORM MUST BE SIGNED

Spot _____ East _____

Expected Spud Date09.....01.....94.....
month day year

.....2,310..... feet from South / North line of Section
1 393 feet from East / West line of Section
IS SECTION X REGULAR _____ IRREGULAR?

OPERATOR: License # ..9534.....
Name: .Giant Exploration & Production Company.....
Address: .P.O. Box 2810.....
City/State/Zip: .Farmington, New Mexico 87499.....
Contact Person: .John C. Corbett.....
Phone: .(505) 326-3325.....

(NOTE: Locate well on the Section Plat on Reverse Side)
County:Meade.....

Lease Name: ..Adams..... Well #: ..32H.....
Field Name: ..Adams Ranch West.....

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): .Lansing, Marmaton, St. Louis.....

CONTRACTOR: License #: Berndt Rig
Name: .Not available at this time.....
ADVISE PRIOR TO SPUD

Nearest lease or unit boundary: ..330'.....
Ground Surface Elevation: ..2548'..... feet MSL

Water well within one-quarter mile: X yes X no
Public water supply well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment:
X. Oil X Enh Rec X Infield X. Mud Rotary
X. Gas X Storage X Pool Ext. X Air Rotary
X OMWO X Disposal X Wildcat X Cable
X Seismic; X # of Holes X Other

Depth to bottom of fresh water: ..220'.....
Depth to bottom of usable water: 520 580

Surface Pipe by Alternate: X. 1 X. 2
Length of Surface Pipe Planned to be set: (1,500) 200

Length of Conductor pipe required: (75')
Projected Total Depth: ..6,400'.....

Formation at Total Depth: .St. Louis.....
Water Source for Drilling Operations:

D.N.R.# ? X. well X. farm pond X. other

If OMWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Will Cores Be Taken?: yes X no X
If yes, proposed zones:
600' Alt. I Req.

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:

Bottom Hole Location:
Exp. 2/1/95

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher David Ricc
SPUD DATE 12-1-94 INIT. R.C.
LENGTH SURFACE PLANNED 1500
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 1523 CONDUCTOR 40'-20"
ANHYDRITE T- B ELEVATION
TD 6450 FORMATION St. Louis
RAN PIPE @ 6362 DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ _____ Ft. W/ SX
Tarranto-120'
Hug./Council @ _____ Ft. W/ SX
126 yds
270 ft
1 Anhydrite Base @ 1530 Ft. W/ S0 SX
1/2 Base Anyh. @ _____ Ft. W/ SX
2 1/2, 1/2 Plug @ 600 Ft. W/ 40 SX
3 Bottom Surface @ 40-0 Ft. W/ 10 SX
40' Plug @ _____ Ft. W/ SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL yes SX (Irr. Well _____ Pond _____)
TECHNICIAN SD DATE 12/15/94 Hauling
TYPE OF CEMENT 60/40 P02 60%
STARTING TIME 8:00 (AM/PM) DATE 12-17
COMPLETION TIME 2:00 (AM/PM) DATE 12-18
CEMENT COMPANY Paul H. Curtis